

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20137-00-00
Spot: NENESWSE Sec/Twnshp/Rge: 22-31S-39W
1250 feet from S Section Line, 1400 feet from E Section Line
Lease/Unit Name: MARGARET E PRICHARD Well Number: 2-A
County: STEVENS Total Vertical Depth: 2940 feet

Operator License No.: 5952
Op Name: AMOCO PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 640 WITH 400 SX CMT
Production: Size 5.5 feet: 2940 WITH 510 SX CMT
Liner: Size feet: \$ 95.55

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/14/2001 9:00 AM
Plug Co. License No.: 5287 Plug Co. Name: HALLIBURTON SERVICES
Proposal Rcvd. from: SPANKY Company: BP AMOCO Phone: (316) 356-6955

Proposed Plugging Method: SET CIBP @ 2490' & 2 SX CMT. PUMP 500# HULLS & 25% OVER CAPACITY ON LONG STRING. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 08/14/2001 10:45 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 2939'. PERFS AT 2714-2856'. TOP FISH @ 2543'. SET CIBP @ 2490' WITH 2 SX CMT. PUMPED 187 SX CMT WITH 500# HULLS DOWN 5 1/2" TO 1590'. PRESSURED TO 250#. FILLED 5 1/2" TO SURFACE. RU TO ANNULUS & PUMPED 28 SX CMT. PRESSURED TO 300#.


RECEIVED
AUG 16 2001
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 3% CC BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

INVOICED

AUG 14 2001

DATE

8-16-01

INV. NO.

2002060251 MP

Form CP 2/3