

To: 1 020740 2-4
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

Drill completion date 9/18/60
API NUMBER 15- 189-10007-0000
C NW, SEC. 35, T 31 S, R 39 W/X
3960 feet from S section line
3960 feet from E section line
Lease Name Youngren Well # 1-35
County Stevens
Well Total Depth 3110 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 615

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Anadarko Petroleum Corp. License Number 4549
Address P.O. Box 351, Liberal, KS 67905-0351

Company to plug at: Hour: 1 p.m. Day: 3 Month: 2 Year: 19 94
Plugging proposal received from Jack Teman
(company name) D & S Cementing (phone) 316-544-7240

Work: 4 1/2" at 2983' w/150 sx cement, PBTD 2928', Perfs at 2768-2917'
1st plug tag tubing top and put 50 sx cement on top,
2nd plug pump 50 sx cement at 656',
3rd plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____
Operations Completed: Hour: 1:45 p.m. Day: 4 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug tagged fish at 2044' and pumped 50 sx cement at 2013',
2nd plug pumped 50 sx cement at 656',
3rd plug pumped 10 sx cement at 40 to -4'.

RECEIVED
STATE CORPORATION COMMISSION
FEB 10 1994
2-10-94
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used Class H cement by D & S Cementing. Recovered 656' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICE
FEB 11 1994
DATE (did / observe) observe this plugging.
INV. NO. 39910
2-4

Signed Glenn R Barlow
(TECHNICIAN)