

1031523

TO: STATE CORPORATION COMMISSION

9-8

API NUMBER 15-189-22,313-6360
NE NE SE SEC. 36, T 31 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HJV CAVNER "B" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STEVENS

OPERATOR LICENSE # 4549

WELL TOTAL DEPTH 6180 200.85 FEET

OPERATOR: ANADARKO PETROLEUM CORP PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 351 SURFACE CASING: SIZE 8 5/8" @ 1670' WITH SX

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CHEYENNE DRILLING LICENSE NUMBER 5382

ADDRESS 3728 W JONES AVE, GARDEN CITY, KS 67846

COMPANY TO PLUG AT: HOUR: 12:30 PM DAY: 08 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM JIM BARLOW

(COMPANY NAME) CHEYENNE DRILLING (PHONE) 316-277-2062

WERE:

9-13-99

1ST PLUG AT 2670' WITH 80 SX CEMENT. 2ND PLUG AT 1690' WITH 50 SX CEMENT.

3RD PLUG AT 690' WITH 30 SX CEMENT. 4TH PLUG AT 40'-0' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 08 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2670 WITH 80 SX CEMENT. 2ND PLUG AT 1690' WITH 50 SX CEMENT.

3RD PLUG AT 690' WITH 30 SX CEMENT. 4TH PLUG AT 40'-0' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY DOWELL.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

DATE 9-14-99 DID NOT OBSERVE THIS PLUGGING.

SIGNED Steve Durrant (TECHNICIAN)

FORM CP-2/3

INV. NO. 60512

RECEIVED
KANSAS CORP COM
1999 SEP 13 1:28

(H)