

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

10-9

2-010182

API Number: 15-191-21069-0000

NE SE NW SECTION 35 TWP 30 RANGE 02W

OPERATOR LICENSE #4419 3630 FEET FROM S SECTION LINE  
OPERATOR BEAR PETROLEUM, INC. 2970 FEET FROM E SECTION LINE  
NAME & P.O. BOX 438  
ADDRESS HAYSVILLE, KS 67060

LEASE NAME RUSSELL #1  
COUNTY SUMMER 123,99  
WELL TOTAL DEPTH 3815' (3785')  
PIPE  
SURFACE CASING 8 5/8" @ 453'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: GRESSEL OIL FIELD SERVICE, INC.

ADDRESS: BOX 607, BURRTON, KS 67020 LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 16:00 DAY: 9 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: DICK SCHREMMER

COMPANY NAME: BEAR PETROLEUM, INC. PHONE: (316) 524-1225

WERE: SAND TO 3722' AND TOP WITH 4 SACKS CEMENT. SHOOT OFF PIPE AND PULL SAME. RUN TUBING TO 453' AND SPOT 35 SACKS CEMENT. PULL TUBING TO 250' AND CIRCULATE CEMENT TO THE SURFACE. 4 1/2" CASING AT 3814'. PERFORATIONS AT 3772' TO 3776'.

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 06 1998

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL  PART  NONE  WICHITA, KS

COMPLETED: HOUR: 17:30 DAY: 9 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT: SANDED TO 3720' AND TOPPED WITH 4 SACKS CEMENT. SHOT PIPE OFF AND PULLED SAME. RAN TUBING TO 455' AND SPOTTED 35 SACKS CEMENT. PULLED TUBING TO 250' AND CIRCULATED 75 SACKS CEMENT TO SURFACE.

REMARKS: USED COMMON CEMENT WITH 4% GEL BY ELMORE'S ACID SERVICE - INVOICE #2679

I DID NOT OBSERVE THIS PLUGGING.

Michael R. Wilson  
MICHAEL R. WILSON

FORM CP-2/3  
REV. 3/90

11-9-98  
60284