

7-27-88 15-191-2015-0000

To: 2 040431
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
^{150'E} NW NW NW SEC. 13, T 30 S, R 2 W/E
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5050
Operator: Hummon Corp.
Name & Address 400 One Main Place
Wichita, KS 67202

Lease Name Meredith Well # 1
County Sumner 135.36
Well Total Depth 4165 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8-5/8 feet 252

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Gressel Corp License Number 5822

Address Haysville, KS

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Curtis L.

(company name) Gressel Corp. (phone) _____

were: PBTD 3265 Sand to 3000' & 5 sx
5-1/2 3808 Bridge at 310' & fill w/redi mix

Perf .3034-38
3152-56
3124-30
3166-70

Plugging Proposal Received by John S.
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 15:00 Day: 27 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT The perforations were covered from 3265' to 3000' and capped with 5 sx cement thru the dump bailer. The 5-1/2 was shot off and recovered from 1872'. A bridge was built at 310' and filled to surface with 4-1/2 yds of redi mix cement.

Remarks: Wellington Redi-Mix #61023
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 8-4-88
INV. NO. 21749

Signed Steve Van Giesse
(TECHNICIAN)