

15-191-00176-0001
7-29-88

X 2 100352

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Sept 23, 68

SE SE SE, SEC. 11, T 30 S, R 2 WXX

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name McLaughlin Well # 10 OWWO

Operator: Hummon Corp.

County Sumner 135.07

Name & Address 400 One Main Place

Well Total Depth 4156 PBD 3386 feet

Wichita, KS 67202

Conductor Pipe: Size 5-1/2 feet 3421

316-263-8521

Surface Casing: Size 8-5/8 feet 313

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated Perf 3202-05

Plugging Contractor Gressel Corp License Number 5822

Address Box 322 Haysville, KS 67060

Company to plug at: Hour: 2:45 Day: 29 Month: 7 Year: 19 88

Plugging proposal received from Kenny

(company name) Gressel Corp (phone) 316-773-1247

were: Sand back to 3150 and dump 5 sx w/bailer. Shoot & pull 5-1/2 bridge at 370' and fill w/redi mix to surface.

Plugging Proposal Received by Sanders

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:00 Day: 29 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT Sanded to 3175 and dump w/bailer 5 sx of cement. Shot 5-1/2 at 1650' and pulled. Set bridge for 375 to 370 and filled with 5-1/2 yards redi mix.

RECEIVED
STATE CORPORATION COMMISSION

8-4-88 AUG 4 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Wellington Redi Mix
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Johnny Sanders (TECHNICIAN)

INVOICED
DATE 8-9-88
INV. NO. 21821