

4-11

2-040533

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-191-20,247 - 0000

30' N of NE NE NW, SECTION 28 TOWNSHIP 30 RANGE 3W

OPERATOR LICENSE # 4569 4980 FEET FROM S SECTION LINE
2970 FEET FROM E SECTION LINE

OPERATOR Jay Boy Oil Co.
NAME & 224 E. Douglas, #425
ADDRESS Wichita, KS 67202

LEASE NAME: Beal #1
COUNTY: Sumner
WELL TOTAL DEPTH: 4334'
CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 222'

140.86

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Rockhold Engineering
ADDRESS: Great Bend, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: _____
COMPANY NAME: _____ PHONE: _____

WERE: 4-1/2" @ 4334' - PBTD 4294' - Perfs 4267-69' - sand to 4200' & 4 sx - 25 sx @ 1000' - 25 sx @ 600' - circ 300' to 0.

PLUGGING PROPOSAL RECEIVED BY: John Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 17:00 DAY: 11 MONTH: 4 YEAR: 1990

ACTUAL PLUGGING REPORT:
The perforations were covered off w/sand to 4200' & capped w/4 sx cmt - 4-1/2" shot loose at 4240' & pulled to 1000' - 25 sx plug - 4-1/2" pulled to 600' & 25 sx plug - 4-1/2" pulled to 300' & cmt cir to surface.

REMARKS: Howco #881866 60/40 4% gel
I DID OBSERVE THIS PLUGGING.

RECEIVED
STATE CORPORATION COMMISSION
Steve Van Gieson
Steve Van Gieson (AGENT)

INVOICED
MAY 9 1990
CONSERVATION DIVISION
Wichita, Kansas
DATE 5-16-90
INV. NO. 28157

FORM CP-2/3
REV. 3/90