

12-23

2-100667 285 R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-191-22,183-0000

NW SE, SECTION 30 TOWNSHIP 30 RANGE 4W

OPERATOR LICENSE # 5151 1980 FEET FROM S SECTION LINE
1980 FEET FROM E SECTION LINE

OPERATOR Gear Petroleum Co., Inc.
NAME & 125 N. Market, #1075
ADDRESS Wichita, KS 67202

LEASE NAME: H-J Farms #1
COUNTY: Sumner
WELL TOTAL DEPTH: 4639' 150.76

CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 265'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Red Tiger Drilling Co.
ADDRESS: Wichita, KS LICENSE: 5302

COMPANY TO PLUG AT: HOUR: 9:00p DAY: 23 MONTH: 12 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Mike Rempe

COMPANY NAME: Red Tiger Drilling PHONE: _____

WERE: 50 sx @ 1250' - 50 sx @ 750' - 35 sx @ 330' - 20 sx @ 60' - 10 sx R.H.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 9:30p DAY: 23 MONTH: 12 YEAR: 1990

ACTUAL PLUGGING REPORT:
Filled hole w/mud & pulled pipe to 1250' - spotted 50 sx cmt - pulled pipe to 750' - spotted 50 sx cmt - pulled pipe to 330' - spotted 35 sx cmt - circ 20 sx cmt to surface from 60' - put 10 sx in rat hole.

REMARKS: Allied #8333 60/40 4% gel

I DID NOT OBSERVE THIS PLUGGING.

Wichita, Kansas
CONSERVATION DIVISION
JAN 4 1991

J. L. Sanders
J. L. Sanders (AGENT)

INVOICED

FORM CP-2/3
REV. 3/90

STATE CORPORATION COMMISSION
DATE 1-28-91
INV. NO. 30562

20