

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mull Drilling Company Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name Ternes Well No. # 1

Location C SW SW Sec. 17 Twp. 30 Rge. 5 (E) (W) W

County Kingman Total Depth 4562

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 5:00PM Day 15th Month Sept. Year 1964

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cemented with 200 sacks. 3705' of 4 1/2" long
string, cemented with 150 sacks, bringing the top of the cement to 3140'.
Top perforation 3632'. Bottom of the hole was sanded to 3625', and cem-
ented with 3 sacks. Hole was filled with mud to 250', and 10' of rock
bridge, cemented with 25 sacks. Hole was filled with mud to 40', and
10' of rock bridge, cemented with 10 sacks to the base of the cellar.
3010' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 9/16/64

INV. NO. 9818-w

Signed: Archie Elving
Well Plugging Supervisor