

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1966  
6-13-66

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Fink Well No. # 2

Location C SE SW Sec. 8 Twp. 30 Rge. 5 (E) (W) W

County Kingman Total Depth 3680'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Pickrell Drilling Company

Address: 705 Fourth National Bank Bldg., Wichita, Ks. License No. \_\_\_\_\_

Operation Completed: Hour 3:00PM Day 1st Month June Year 1966

The Above well was plugged as follows:

203' of 8 5/8" surface pipe, cement circulated with 155 sacks. Hole  
was filled with drilling mud to 200', 1st cementing plug, bridged  
with 2 sacks of dry cement and 1/2 sack of hulls on fluid at 200', and  
cemented with 23 sacks. Hole was filled with drilling mud to 40', 2nd  
cementing plug, bridged with 1 sacks of dry cement, and 1/2 sack of hulls  
on fluid at 40', and cemented with 9 sacks to the base of the cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlie Elving  
Well Plugging Supervisor

DATE 6-13-66

INV. NO. 3387-W