

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-119-20,467-0000 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR H & I Inc. OPERATORS LICENSE NO. 7123

ADDRESS Box 1532 Liberal, Kansas 67901 PHONE # (316) 624-2069

LEASE (FARM) Bender WELL NO. 1 WELL LOCATION C SW SW COUNTY Meade

SEC. 21 TWP. 32 S RGE. 30 W (S) or (W) TOTAL DEPTH 6050 PLUG BACK TD 4795

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8 SET AT 1562 CEMENTED WITH 800 SACKS

CASING SIZE 4 1/2 SET AT 5910 CEMENTED WITH 350 SACKS

PERFORATED AT 4727 - 4731

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 20 sks. of cement @ 4731 to 4627

40 sks. of cement @ 1592 to 1492 25 sks. of cement @ 750 to 650

Put 10 sks. of cement @ 40 to 0

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes No IS ACO-1 FILED?
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon Approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Box PHONE # (316) 624-2069

ADDRESS 1731 N. Cain Liberal, Kansas 67901

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547

ADDRESS Box 506 Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Robert Sargent
(Operator or Agent)

DATE: 11-17-86

①

RECEIVED

11-18-86

NOV. 28 1986



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1288

THIS NOTICE

FEB 18 '87

EXPIRES

November 18, 1986

WELL PLUGGING NOTICE

Bender #1
C SW SW
Sec. 21-32S-30W
Meade County

H & I Inc.
Box 1532
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).

TUCKER PRODUCTION CORP.
BOX 6

REPLACEMENT CARD:
#1 BENDER

21-32-30W
C SW SW

LIBERAL, KS. 67901

CONTR NRG DRILLING INC. CTY MEADE

GEOL _____ FIELD STEVENS

E 2773 KB CM 4/18/81 CARD ISSUED 7/9/81 IP SIGW

MRW 5564-5566

+	+
+	+
*	+

API 15-119-20,467

SMP	TOPS	DEPTH	DATUM
CO GR		3047	- 274
HEEB		4359	-1586
LANS		4473	-1700
KC		4729	-1956
HODGES		4927	-2154
MARM		5098	-2325
CHER		5273	-2500
MRW		5565	-2792
CHEST		5654	-2881
STE GEN		5842	-3069
ST L		5935	-3162
TD		6050	-3277

8-5/8" 1562, ~~4-1/8~~ 5910
DST (1) 4688-4740/30-60-60-120, REC 160'
GCM, 430' SW, SIP 1064-1064#, FP
58-145/174-260#, HP 2183-2183#
DST (2) 5546-5593/30-60-60-120, GTS 2",
GA 3.036 MCFG DECR TO 1949 MCFG ON
(2ND OP), REC 780' SW, SIP 1363-
1379#, FP 766-666/666-666#, HP
2746-2693#
DST (3) 5626-5638/30-60-40-120, REC
5' DM, SIP 147-147#, FP 30-30/30-
30#, HP 2679-2649#
MICT - CO, PF 9/5564-5566, KO F, NAT,
SI

CORRECTION: 12/3/81 - WAS C SW/c

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

15-119-20467-0000