

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-025-00019-0000

Operator's Full Name Frank J. Black

Complete Address: Box 150, McPherson, Kansas

Lease Name Strodtman Well No. 1

Location C SE NW Sec. 3 Twp. 31 Rge. 21 (E) (W)

County Clark Total Depth 5218'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kansas License No. 436

Operation Completed: Hour 4:15PM Day 30 Month 5 Year 1966

The Above well was plugged as follows:

20" Casing to 110' circulated w/ cement. 5 1/2" to 5195' cemented.

No Perforations, Plug bottom w/ sand & 5 sacks of cement.

Top of cement 5150' Mud 5150' to 600'

Spot 30 sacks cement 600' to 500' Mud 500' to 130'

Spotted 40 Sacks cement 130' to 80' Mud 80' to 30'

Plug & 30 sacks cement 30' to 0' Company Pump.

Pulled 3385' of 5 1/2" casing.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUN - 3 1966

Signed: Edmund J. Jones
Well Plugging Supervisor

DATE 6/3/66

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 3330-U