

15-097-20374-00-2

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
Form CP-3  
MAR 07 1977  
3-07-77  
CONSERVATION DIVISION  
Wichita, Kansas  
6-4-68

R

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Imperial Oil Co.  
Complete Address Box 784, Great Bend, Kans  
Lease Name Slief Well No. 1-7  
Location NE NE NW Sec. 7 Twp. 29 Rge. 20 (E) (W) X  
County Kiowa Total Depth 5125  
Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Kelso Casing Pulling  
Address Box 176 Chase, Kansas License No. 683  
Operation Completed: Hour 10:00am Day 3 Month March Year 1977

The above well was plugged as follows:

564' OF 8 5/8 SURFACE CEMENTED WITH 250 SKS, 5122' OF  
4 1/2 LIND. STRING CEMENTED WITH 200 SKS. P.B. 5119, PERFOR.  
5102 TO 5112, SAND BACK TO 5045', 4 SKS CEMENT WITH  
BAITEN, RECOVERED 4220' OF 4 1/2, PUMPED 1,5 K. HULL, 18  
SKS OF GEL, RELEASED PLUG, PUMPED 80 SKS CEMENT 50-50, POS.  
PUMPED 7 GEL, 1,5 K. HULLS 20 SKS CEMENT 50-50 POS.

PUMPED BY SUN CEMENTING CO.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: J. H. [Signature]  
Well Plugging Supervisor

DATE 3-7-77

INV. NO. 4748-4