

 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

DEC 14 1966  
12-14-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Leben Drilling, Inc.

Complete Address: 815 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Becker Well No. # 1

Location 150'SW of C SW NE Sec. 8 Twp. 28 Rge. 12 (E) (W) W

County Pratt Total Depth 4595'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 2:30PM Day 13th Month Dec. Year 1966

The Above well was plugged as follows:

360' of 8 5/8" surface pipe, cement circulated with 350 sacks. Fluid  
level in the hole was at 120'. 1st cementing plug and 1/4 sack of hulls  
was pushed in fluid to 300', and cemented with 25 sacks, through the  
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid  
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 12/14/66

INV. NO. 4461-11