

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten signature]

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

15-129-00106-0006
FILE NO. 116-41
LOCATION N8-N8-SW
SEC. 34 TWP. 31 RGE. 43W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Dreyer "B"

Operator Colorado Oil & Gas Corp. Address Box 999, Liberal, Kans.

Field _____ County Morton

Total Depth 3413 Feet.

Plugging Contractor Forbes Casing Pulling Co.

Plugging Contractor's License No. 49

Address Great Bend, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 596' c.w.c. 5 1/2" casing set
3411' Cem. by temp. survey 2040' outside 5 1/2" casing.
All perforations squeezed off. Baker plug @
2610' w/ 2 st Counsel. Pulled 5 1/2" casing.
Filled hole with heavy mud to 595' set
rock bridge and run 20 st Cem. mud to
35' rock bridge and 10 st Cem. to base of cellar

Warren H. Horner
District Conservation Agent

Date May 28, 1955

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 - 1955
CONSERVATION DIVISION

PLUGGING
FILE SEC. 34 TWP. 31 R. 43W
BOOK PAGE 116 LINE 41