


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-189-30103-0000 Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stevens County. Sec. 25 Twp. 31S Rge. 39 (X) W (W)  
Location as "NE/CNW/SW" or footage from lines 1250' FWL & 1390' FSL  
Lease Owner Anadarko Production Company  
Lease Name Simmons "B" Well No. 2  
Office Address Box 351, Liberal, Kansas 67901  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed 12-20 19 67  
Application for plugging filed 5-28 19 69  
Application for plugging approved 6-2 19 69  
Plugging commenced 6-30 19 69  
Plugging completed 6-30 19 69  
Reason for abandonment of well or producing formation Non-economical

If a producing well is abandoned, date of last production February 19 68  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves  
Producing formation Council Grove Depth to top 2703' Bottom 2854' Total Depth of Well 2900 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Council Grove	Gas	2703	2854	8 5/8"	608'	None
				5 1/2"	2898'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mixed 15 sacks of cement  
Pumped plug to 2560'  
Spotted 20 sacks cement from 440' to 600'  
Spotted 5 sacks cement from 40' to surface  
Completed 6-30-69

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 11 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Sargent's casing Pulling Service  
Address 102 W. Walnut, Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward, ss.

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. K. Downey  
Box 351, Liberal, Kansas 67901  
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of July, 19 69



John E. Shockley  
Notary Public.

15-189-3103-0000

DRILLER'S LOG

WELL NAME: Simmons "B" No. 2 ; COMPANY OPERATING: Anadarko Production Company  
 ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901

WELL LOCATION: SE 1/4 NW 1/4 SW 1/4,  
1390 ft. North of South line,  
1250 ft. East of West line: Sec. 25, Twp. 31S, Rge. 39W, Stevens County, Kansas

DRILLING STARTED 3-3, 1967; DRILLING COMPLETED 3-7, 1967  
 WELL COMPLETED 12-20, 1967; WELL CONNECTED 12-20, 1967

ELEVATION: 3184 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Gas

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Council Grove	2703	2854	62	2000	15% regular
				80,000	gelled water

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 2 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	608	400 sxs	
5 1/2"	2898	320 sxs	
2 3/8	2860	-	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand, Gravel & Red Bed	0'	609'			
Red Bed	609'	695'			
Red Bed & Sand	695'	1375'			
Sand	1375'	1972'			
Red Bed	1972'	2332'			
Shale & Anhydrite	2332'	2592'			
Anhydrite	2542'	2765'			
L.S.	2765'	2849'			
Lime	2849'	2900'			
R.T.D.		2900'			

RESULTS of INITIAL PRODUCTION TEST: \_\_\_\_\_