

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-189-223130000

LEASE NAME HJV CAVNER "B"

WELL NUMBER 1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 36 TWP. 31 RGE 39 (E) or (W)

COUNTY STEVENS

Date Well Completed 9/7/1999

Plugging Commenced 9/8/1999

Plugging Completed 9/8/1999

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/7/1999 (date)

by MR. MARK MAIER (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 6180

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1670'	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. TIH W/4 1/2" DP TO 2670' & SPOT 80 SKS 60/40 POZMIX, 6%GEL @ 2670', TOH TO 1690' & SPOT 50 SKS, TOH TO 690' & SET 30 SKS, TOH TO 40' & SET 10 SKS FROM 40' TO 0'. SET 10 SKS IN MH & 15 SKS IN RH. CUT OFF 8-5/8" CSG 3' BELOW GI AND CAP. PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DOWELL-SCHLUMBERGER License No. 116095

Address 204 S. MISSOURI, ULYSSES, KANSAS 67880

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) L. Marc Harvey 9-27-99

L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT
 (Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1999

Shirley J. Childers
 Notary Public

My Commission Expires:



Form CP-4
 Revised 05-88

RECEIVED
 AS CORP FORM
 SEP 30 AM 11:33

ANADARKO PETROLEUM CORPORATION

RECEIVED

KANSAS CORP COMM

PHONE 316 - 624 - 6253 • 1701 NORTH KANSAS AVE. • P.O. BOX 351 • LIBERAL, KANSAS 67905 - 0351

1999 SEP 30 A 11:33



September 27, 1999

Kansas Corporation Commission
Conservation Division
Wichita State Office Building
130 South Market, RM 2078
Wichita, Kansas 67202

Re: HJV Cavner "B" No. 1
Section 36-31S-39W
Stevens County, Kansas

Gentlemen:

Attached is KCC Form CP-4 (Well Plugging Record) on the above referenced well.

If you have any questions, please advise.

Very truly yours,

A handwritten signature in black ink, appearing to read "L. Marc Harvey", is written over a horizontal line.

L. Marc Harvey
Drilling Technical Assistant
LMH/sh

Enclosures

cc: Well File
TRC - HGO
Manager Land Administration - HGO
WI Owners