


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-175-60450-0000
WELL PLUGGING RECORD

SEWARD County, Sec. 24 Twp. 31S Rge. 32W (W)

Location as "NE/CNW/SW" or footage from lines C NE
Lease Owner Graham-Michaels Drilling Co.
Lease Name GARTEN Well No. 1
Office Address 211 North Broadway, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Low Production
Date well completed 11-19-57 19__
Application for plugging filed 10-21-57 19__
Application for plugging approved 11-16-57 19__
Plugging commenced 11-16-57 19__
Plugging completed 11-19-57 19__
Reason for abandonment of well or producing formation Low Production

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production none 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2743 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Soil, Sand, Clay,</u>						
<u>Gyp & Red Bed</u>		<u>0</u>	<u>563</u>	<u>8 5/8"</u>	<u>563*</u>	<u>•</u>
<u>Shale, Lime</u>		<u>0</u>	<u>2743*</u>	<u>5 1/2"</u>	<u>2743*</u>	<u>904*</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back w/crushed rock to 2625*, dumped 5 sax cement @2625* w/dump bailer. Top of cement, 2590*. Filled hole w/mud to 560*, set rock bridge, dumped 20 sax cement. Top of cement, 500*. Filled hole w/mud to 35*, set rock bridge, dumped 10 sax cement for cap.

STATE COMMISSION
12-3-57
DEC 5 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company
Address P. O. Box 771, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
O. W. Woodland (employee of owner) ~~not sworn to~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Graham-Michaels Drilling Co.

(Signature) O. W. Woodland

211 North Broadway, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 1957

T. D. Guier
Notary Public.

My commission expires 1/7/61

PLUGGING
FILE SEC 24 T. 31 R. 32W
BOOK PAGE 55 LINE 14

