

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-21163-0000

LEASE NAME Howard

TYPE OR PRINT

WELL NUMBER 1

NOTICE: Fill out completely  
and return to Cons. Div. E  $\frac{1}{2}$  E  $\frac{1}{2}$  NE Ft. from S Section Line  
\_\_\_\_\_ Ft. from E Section Line

LEASE OPERATOR Berexco, Inc.

SEC. 21 TWP. 31 RGE. 33 (E) or (W)

ADDRESS P.O. Box 723 Hays, Kansas 67601

COUNTY Seward

PHONE # (313) 628-6101 OPERATORS LICENSE NO. 5363

Date Well Completed 7/24/91

Character of Well D&A

Plugging Commenced 1-29-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-30-92

The plugging proposal was approved on 1-29-92 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? \_\_\_\_\_

Producing Formation MORROW Depth to Top 5471 Bottom 5480 T.D. 5900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD | RECEIVED STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1610	0
				4 1/2	5903	2204

FEB 17 1992  
CONSERVATION DIVISION  
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Pump 30 sks. of cement & 1 sk of bulls to 5350  
Pump 50 sks. of cement from 1640 to 1440  
Pump 40 sks. of cement from 700 to 550  
Put 10 sks. of cement from 40 to 0 Cut off 7 cao 8 5/8 4' below ground level  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Evan C Mayr

(Address) 970 Fourth Fin. Ctr., Wichita, KS

SUBSCRIBED AND SWORN TO before me this 14th day of February, 1992



Betty J. Terbush  
Notary Public

My Commission Expires: 4-11-92