

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-21,224-00-00

LEASE NAME Davis "L"

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1200 Ft. from S Section Line

4620 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 3 TWP. 31S RGE. 34 (S) or (W)

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

COUNTY Seward

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 12-7-91

Character of Well D&A

Plugging Commenced 12-7-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-7-91

The plugging proposal was approved on 12-6-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1636'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Spotted 100 sxs cmt plug @ 2850', 50 sxs cmt plug @ 1650', 50 sxs cmt plug @ 750', 10 sxs cmt plug @ 0-40', 15 sxs in rathole, 10 sxs in mousehole. Pump heavy drlg mud between each plug. Cmt w/60/40 Poz, 6% total gel. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gabbert-Jones, Inc. License No. 5842

Address 333 East English, Suite 215, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters contained and the log of the above-described well as filed that the same are true in my hand and in the presence of me, God.

RECEIVED
KANSAS CORPORATION COMMISSION

1-24-92
JAN 24 1992

(Signature) Beverly J. Williams

(Address) Beverly J. Williams, Eng. Tech.
P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 22 day of January, 1992

CONSERVATION DIVISION
WICHITA, KS

Cheryl Steers
Notary Public

My Commission Expires: _____

A
CHERYL STEERS
Notary Public - State of Kansas
My Appt. Expires 6-1-93