

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North ~~Wade~~ **RECEIVED**
WICHITA, KANSAS 67202
STATE CORPORATION COMMISSION

SEP 30 1977

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-625-20170-0000

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. French of Pickrell Drlg. has this

date requested permission to plug the following described well:

Mr. French guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drlg. Co.

Complete Address: 205 Litwin Bldg., Wichita, Ks.

Lease Name: Ardrey "B" Well No. 3

Location: 150' N of SW NW Sec. 2 Twp. 31 Rge. (E)(W) 24

County: Clark Total Depth 5525' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. French was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 650' thru drill

pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Ben Massey
Conservation Division Agent