



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-119-10084-0000

RECEIVED
 STATE CORPORATION COMMISSION

APR 24 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Gruenerwald of Wm. Gruenerwald has this

date requested permission to plug the following described well:

Mr. Gruenerwald guarantees payment of the plugging fee.

Operator's full Name: Wm. Gruenerwald

Complete Address: 35 E. Wacker Dr. Chicago, Ill.

Lease Name: Miles Well No. # 1

Location: SE/4 Sec. 7 Twp. 31S Rge. 29 (E) (W)

County Meade Total Depth 5485' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Gruenerwald was instructed to plug the well as follows:

8 5/8" 1673' Circulated w/cement. 5 1/2" 5485' Cemented.

Top Perforations 5444'

Plug bottom w/20 Sax.cement 5485' to 5335'. Mud 5335' to 700'

Plug, 35 Sax.cement 700' to 600' Mud 600' to 40'

Plug, 15 Sax.cement 40' to surface.

Very truly yours,

Augh Scott
 Conservation Division Agent