



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-119-20155-0000

RECEIVED
STATE CORPORATION COMMISSION

JUN 25 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Carmen of National has this

date requested permission to plug the following described well:

Mr. Carmen guarantees payment of the plugging fee.

Operator's full Name: National Oil Company

Complete Address: 200 W. Douglas, Wichita, Kansas

Lease Name: _____ Miles _____ Well No. 1

Location: C W/2 SE Sec. 7 Twp. 31 Rge. 29 XX (E) (W)

County: Neade Total Depth 5500' Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Carmen was instructed to plug the well as follows:

8 5/8" to 1417' circulated w/ cement. 4 1/2" to 5499' cemented.


Top perforations 5083' Plug bottom w/ 20 sacks cement.

Top of cement 5200' Mud 5200' to 1400'

Spot 35 sacks cement 1400' to 1235' Mud 1235' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent