



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-129-00055-0000

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Gatten of Anadarko Production Co. has this
date requested permission to plug the following described well:

Mr. Gatten guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Cunningham Well No. # 1

Location: C SE NW Sec. 14 Twp. 31 Rge. 41 (E)(W)

County Morton Total Depth 5374' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Gatten was instructed to plug the well as follows:

8 5/8" - 1527' Circulated w/cement.

5 1/2" - 5373' Cemented. Perforations 5359' to 5369'

Plug bottom w/20 Sax. cement top cement 5234'. Mud 5234' to 700'

Spotted 35 Sax. cement 700' to 600'. Mud 600' to 45'

Plug, Hulls, 15 Sax. cement 45' to 0

Very truly yours,

Hugh Scott
Conservation Division Agent