

15-025.26168-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Clark SEC. 4 TWP. 31s RGE. 24w E/W  
 Location as in quarters or footage from lines:  
150' E of C SE SE


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Rains & Williamson Oil Co., Inc.  
 Lease Name Brown - English "A" Well No. 1  
 Office Address 220 W. Douglas, 435 Page Court Bldg, Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole):  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 8/3/83  
 Plugging completed 8/9/83  
 Reason for abandonment of well or producing formation  
Depleted

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 5530'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	328'	none
				4 1/2"	5519 1/2'	3017'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Squeezed casing with 1 hull, & 30 sacks common cement. Pumped plug to  
 5000'. Shot casing at 4500', 3720', 3230', & 3020'. Pulled total of 98  
 joints. Squeezed hole with 3 hulls, 15 gel, 70 cement, 15 gel, & 1 hull.  
 Released plug & displaced with 150 sacks cement.

Plugging complete.

RECEIVED  
 STATE CORPORATION COMMISSION  
 8-16-83 AUG 16 1983  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1983



Irene Hoover  
 Notary Public.

My Commission expires: \_\_\_\_\_

DRILLER'S LOG

15-025-20168-0000

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 4 T. 31S R. 24W

LOC. 150' E of C SE SE

WELL NAME: Brown-English 'A' #1

COUNTY: Clark

RIG NO. #2

TOTAL DEPTH 5530'

ELEVATION 2559 GL 2569 KB

COMMENCED: 9-12-77

COMPLETED: 9-25-77

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 328' w/250 sx. common, 3% cc.

PRODUCTION: 4 1/2" @ 5519.50' w/150 sx. 60/40 poz., 12% salt, 3/4 of 1% CFR2.

LOG

(Figures Indicate Bottom of Formations)

Clay, Sand & Shale	305
Sand & Shale	1105
Shale	2435
Shale & Lime	4100
Lime	4565
Sand & Shale	4715
Shale	4900
Shale & Lime	4961
Lime	5530
<u>ROTARY TOTAL DEPTH</u>	<u>5530</u>


STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.  
upon oath state that the above and foregoing is a true and correct copy of the log of the  
Brown-English 'A' #1 well.

Wilson Rains  
Wilson Rains



Subscribed and sworn to before me this 28 day of September, 1977.

STATE CORPORATION COMMISSION

My Appointment Expires:

**JUN 13 1983**

10-4-79

CONSERVATION DIVISION  
Wichita, Kansas

Juanita M. Green  
Juanita M. Green