


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

CLARK County. Sec. 4 Twp. 31S Rge. 24W E/A  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
SW NE  
Lease Owner PICKRELL DRILLING COMPANY  
Lease Name McFadden "D" Well No. 1  
Office Address 205 LITWIN BLDG., WICHITA, KS. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above Section Plat

DRY HOLE  
Date Well completed 12-13-78 19  
Application for plugging filed 12-13-78 19  
Application for plugging approved 12-13-78 19  
Plugging commenced 12-13-78 19  
Plugging completed 12-13-78 19  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.  
Producing formation Depth to top Bottom Total Depth of Well 5620  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	504	Mpme

Describe in detail the manner in which the well was plugged, indicating where the mud flux was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

40 sacks at 700'  
40 sacks at 510'  
12 sacks at 40' with solid bridge plug  
3 sacks in Rat Hole Comp. 10:30AM 12/13/78

RECEIVED  
STATE CORPORATION COMMISSION  
12-22-78  
DEC 22 1978

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PICKRELL DRILLING COMPANY

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
C. W. Sebitts (employee of owner) or (owner or operator)

I, the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God. By: C. W. Sebitts

(Signature)

205 LITWIN BLDG., WICHITA, KS. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of December, 19 78

Jo Ann Sarver  
Notary Public.

My commission expires



**ROTARY DRILLING LOG**

COMPANY: PICKRELL DRILLING COMPANY  
 205 LITWIN BLDG.  
 WICHITA, KS. 67202  
 LOCATION: McFadden "D" #1  
 SW NE Sec. 4-31S-24W  
 Clark Co., Kansas  
 CONTRACTOR: **PICKRELL DRILLING COMPANY**  
 Wichita, Kansas

Rotary Drilling Commenced 11-30-78  
 Rotary Drilling Completed 12-13-78  
 15-025-26242-0000

CASING RECORD: Surf. casing 8 5/8" set at 504' with 300sx. Comp. 8:30 pm 11-30-78

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Shale & Sd. Stks	490
Red Beds	512
Shale	715
Shale	1555
Shale	2041
Lime Stks & Shale	2370
Shale & Lime	2660
Lime & Shale	2790
Lime	2900
Lime & Shale	3075
Lime & Shale	3195
Lime & Shale	3340
Lime & Shale	3495
Lime & Shale	3660
Lime & Shale	3818
Lime & Shale	3950
Lime & Shale	4085
Lime & Shale	4202
Lime & Shale	4305
Lime & Shale	4460
Lime & Shale	4605
Lime & Shale	4715
Lime & Shale	4850
Lime & Shale	4960
Lime	5035
Lime & Shale	5060
Lime & Shale	5149
Lime	5225
Lime	5260
Lime	5275
Lime & Shale	5360
Lime	5428
Lime	5485
Lime	5487
Lime	5501
Lime	5550
Lime	5620

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 22 1978  
 CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
 By *C. W. Sebitts*  
 Attorney-in-Fact  
 C. W. Sebitts

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } ss.:

On this 20 day of December, 1978, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: \_\_\_\_\_

*Jo Ann Sarver*  
 Notary Public  
 Jo Ann Sarver

