

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 189-20,696-0000

LEASE NAME Brollier

WELL NUMBER 1-28

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

C NE NE Ft. from S Section Line  
660

660 Ft. from E Section Line

SEC. 28 TWP. 31S RGE. 35W (E) or (W)

COUNTY Stevens

Date Well Completed 8-17-84

Plugging Commenced 11-7-84

Plugging Completed 11-9-84

LEASE OPERATOR Energy Corp.  
Flynn Energy

ADDRESS Rt. 1 Hennessey, Oklahoma 73742

PHONE# (918) 749-0469 OPERATORS LICENSE NO. 6958

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top 6014 Bottom 6020 T.D. 6100

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Chester Sand</u>	<u>Oil &amp; Water</u>	<u>6014</u>	<u>6020</u>	<u>8 5/8</u>	<u>1725</u>	<u>none</u>
				<u>4 1/2</u>	<u>6100</u>	<u>3028</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Pump 20 sks. of cement @ 6020 to 5800

Pump 25 sks. of cement @ 2600 Put 10 sks. of cement @ 40 to 0

Pump 25 sks. of cement @ 1780 Cut off & cap 8 5/8 3' below ground level

Pump 20 sks. of cement @ 680

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 647

Address Box 506 Liberal, Kansas 67901 12-10-84 DEC 10 1984

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

CONSERVATION DIVISION  
Wichita, Kansas

RICHARD R. LUCE (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard R. Luce

(Address) 2431 East 61st, Suite 150

Tulsa, OK 74136

SUBSCRIBED AND SWORN TO before me this 6th day of December, 1984

Quenna Rugga  
Notary Public

My Commission Expires: 6/24/86