

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20546-0000

LEASE NAME Brollier

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div. C
office within 30 days.

WELL NUMBER 28-1

NE NE Ft. from S Section Line

 Ft. from E Section Line

SEC. 28 TWP. 31S RGE. 35W (E) or (W)

COUNTY Stevens

Date Well Completed

Plugging Commenced 3-14-91

Plugging Completed 3-19-91

LEASE OPERATOR Kansas Exploration Inc.

ADDRESS Box 681 Liberal, Kansas 67905-0681

PHONE (³¹⁶) 624-3871 OPERATORS LICENSE NO. 30631

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 6200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1746	0 5-10-91
				4 1/2	6190	2520 MAY 17 1991
						CONSERVATION DIVISION
						Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 20 sks. of cement from 6035 to 5800

Pump 35 sks. of cement from 2500 to 2400

Pump 50 sks. of cement from 1780 to 1680 Pump 35 sks. of cement from 700 to 600

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 3' below ground level

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547


Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) James F. Stephens

(Address) P.O. Box 681 Liberal, KS - 67905



AND SWORN TO before me this 9 day of May, 19 91

Carol J. Lockas
Notary Public

My Commission Expires: 10-18-91