


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-189-20501-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stevens County. Sec. 29 Twp. 31S Rge. 36 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
50' FSL & 2590' FEL



Lease Owner Texaco Inc.  
Lease Name Moscow SWD Well No. 1  
Office Address Box 2420, Tulsa, OK 74102  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
SWD

Date Well completed 3-20-80 1980  
Application for plugging filed 7-31-81 1981  
Application for plugging approved 8-11-81 1981  
Plugging commenced 8-26-81 1981  
Plugging completed 8-26-81 1981  
Reason for abandonment of well or producing formation \_\_\_\_\_  
would not accept water  
If a producing well is abandoned, date of last production \_\_\_\_\_  
1981

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation Glorietta Depth to top 1172 Bottom 1247 Total Depth of Well 1303  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5-1/2"	1300'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. From 1540-1100' w/30 sx cmt; from 1100-750' w/heavy mud; from 750-450' w/50 sx cmt; from 450-60' w/heavy mud; from 60-4' below ground level w/10 sx cmt.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 16 1981 9-16-81  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sargents Casing Pulling

STATE OF Kansas COUNTY OF Stevens, ss.  
B. A. Batson (employee of owner) ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. A. Batson B. A. BATSON  
Texaco Inc., P.O. Box 2420, Tulsa, OK  
(Address) 74102

SUBSCRIBED AND SWORN TO before me this 14<sup>th</sup> day of September, 1981

Freda Putman  
Notary Public.

My commission expires 12-2-83

TEXACO, INC.

THUROW UNIT O/A #3  
STEVENS COUNTY, KANSAS

15-189-20901-0000

OPERATIONS COMMENCED: 3/12/80

OPERATIONS COMPLETED: 3/16/80

DRILLING LOG

3/13	0 - 670	Sand, Gypsum, Shale, Red Bed
3/14	670 - 1303	Sand, Gypsum
3/15	1303 - 1303	

CASING RECORD

3/13	Ran 16 jts. of new 8 5/8", 24# casing. Set at 670'. Cemented with 250 sks. of 35/65 and 150 sks. of Class H, 3% c.c.
3/15	Ran 31 jts of new 5 1/2", 14# casing. Set at 1303'. Cemented with 150 sks. of 35/65 and 200 sks. of 50/50 Poz, 10% Salt.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 7 1981  
CONSERVATION DIVISION  
Wichita Kansas