

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
30 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-10148 - 0000

LEASE NAME CAVNER

WELL NUMBER 1-35

1324 Ft. from S Section Line

1319 Ft. from E Section Line

SEC. 33 TWP. 31S RGE 38( E ) or ( W )

COUNTY STEVENS

Date Well Completed 2-6-38

Plugging Commenced 1-13-98

Plugging Completed 1-13-98

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on AUGUST 7, 1997 (date)

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation CHASE Depth to Top 2412 Bottom 2638 T.D. 2638

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To   | Size   | Put In | Pulled Out |
|-----------|---------|------|------|--------|--------|------------|
| CHASE     | GAS     | 2412 | 2638 | 10-3/4 | 550    | 0          |
|           |         |      |      | 7      | 2424   | 585        |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. MIRU CP. PMP 4 SXS HULLS & 40 SXS CMT. CHASE CMT PLUG W/WL. CMT WENT BEHIND LINEAR. MIRU WL. SET 7" CTR @ 2406. RDMO WL. ID HOLE W/ 60 BBL MUD. CUT OFF 7" CSG @ 585'. PMP 75 SXS CMT TO PLUG 585-435'. POH W/ 7" CSG TO 40'. PMP 10 SXS CMT TO PLUG 40-0'. POH W/ REMAINING 7" CSG. CUT OFF AND CAP 10-3/4" CSG 4' BELOW GL. RDMO CP. KCC STATE REP. STEVE MIDDLETON & GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC License No. 31151

Address ROUTE 1, BOX 49B, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

5-5-98  
FEB 5 1998

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 1998

Shirley J. Childers  
Notary Public

My Commission Expires: 10/14/98

