

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-223510000

LEASE NAME CAVNER "A"

WELL NUMBER 5

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 33 TWP. 31S RGE. 38 ( E ) or ( W )

COUNTY STEVENS

Date Well Completed 9-20-2000

Plugging Commenced 11-29-2000

Plugging Completed 12-6-2000

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-20-2000 (date)

by MR. STEVE MIDDLETON (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 1401'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	9'	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. TIN W/2-7/8" TO 157'. LOST CIRC. DRY BEAM TO 642'. SPOT 50 SXS CLASS H CMT W/ 10% CAL SEAL, 4% GEL, 10%/SX GILSONITE, & 2% CACL2. TAG TOC @ 241. SPOT 50 SXS 60/40 CMT W/ 6% GEL & 1/2#/SX FLO SEAL. TAG CMT @ 180. SPOT 400 SXS 60/40 CMT W/ 6% GEL & 1/2#/SX FLO SEAL. TAG CMT @ 80. SPOT 50 SXS 60/40 CMT W/ 6% GEL & 1/2#/SX FLO SEAL. CIRC TO SRF. RIH 16' W/ 25' JT 8-5/8" CSG. CUT OFF 8-5/8" CSG 3' BELOW GL AND CAP. PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BIG "A" DRILLING License No. 31576

Address P.O. BOX 1856, LIBERAL, KANSAS 67905-1856

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss CONSERVATION DIVISION

L. MARC HARVEY, ENGINEERING TECHNICIAN III (Employee of Operator) Wichita, Kansas of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey  
L. MARC HARVEY, ENGINEERING TECHNICIAN III  
(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 11th day of December, 2000.

Shirley Childers  
Notary Public  
Form CP-4  
Revised 05-88

My Commission Expires: 11/14/02

NOTARY PUBLIC - State of Kansas  
SHIRLEY J. CHILDERS  
My Appt. Exp. 11/14/02

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 2000