

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-189-30097-0000

API NUMBER NA (SPUD DATE 06/17/66)

LEASE NAME MCCLURE "H"

WELL NUMBER 2

1320 Ft. from S Section Line

200 Ft. from W Section Line

SEC. 34 TWP. 31S RGE 38 (E) or (W)

COUNTY STEVENS

Date Well Completed 06/29/66

Plugging Commenced 03/06/97

Plugging Completed 03/07/97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 02/27/97 (date)

by MR. STEVE DURANT (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation COUNCIL GROVE Depth to Top 2768' Bottom 2936' T.D. 3020'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
COUNCIL GROVE	GAS	2768'	2936'	8-5/8"	638'	0'
				5-1/2"	3019'	0'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU WIRELINE, DUMP 40 BBL WTR & KILL WELL, SET CIBP @ 2700', DUMP 2 SKS CMT ON CIBP, LOAD CSG W/9 PPG MUD, PERF FROM 687-688' W/4 SPF, RDMO WIRELINE, ESTABLISH CIRC TO SURFACE BY PMPG 9 PPG MUD DOWN 5-1/2" CSG AND UP ANNULUS, PREP TO CMT, PMP 250 SKS CMT DOWN 5-1/2" CSG AND UP ANNULUS, SHUT DOWN WHEN CMT CIRC TO SURFACE.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287

Address P.O. BOX 1598, LIBERAL, KS 67905-1598 PHONE: (316) 624-3879

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 7th day of April, 1997

FREDAL HINZ  
Notary Public - State of Kansas  
My Comm. Expires 5-15-99

Notary Public

My Commission Expires:

RECEIVED  
KANSAS CORP COM  
MAY 15 10:33 AM '97  
4-15-97