

SPR

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name W. D. Short

Complete Address: Box 45 - Oxford Kans.

Lease Name Struthers Well No. 1

Location SE-SE-NW- Sec. 2 Twp. 29 Rge. (E) 2 (W)

County Sedgewick Total Depth 3579

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Paul Shepard - Ind. Co.

Address: Winfield Kans. License No. 563

Operation Completed: Hour 5:30 Day 27 Month 3 Year 1966

The Above well was plugged as follows:

Filled hole with sand to 3550 ft.
Mixed and dumped 5 sacks cement.
Pulled 2,980 ft. of 5 1/2" casing.
Set a Rock Bridge from 200 ft. to 185 ft.
Added 20 sacks cement. Muddied hole from
this point to 30 ft. Added 10 sacks cement
to surface.
(450 ft. 8 5/8" surface pipe - Circulated)

I hereby certify that the above well was plugged as herein stated.

INVOICED Paul Shepard

Signed: Paul Turpin
Well Plugging Supervisor

DATE 3-29-66

INV. NO. 4151-E