


15-191-20229-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Sumner County. Sec. 33 Twp. 30S Rge. (E) 3 (W)
Location as "NE/CNWxSWx" or footage from lines C NE NE
Lease Owner Oasis Petroleum, Inc.
Lease Name Bomholt Well No. 1
Office Address 800 Sutton Place, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 22, 1970 1970
Application for plugging filed October 26 1970
Application for plugging approved October 27 1970
Plugging commenced October 27 1970
Plugging completed October 29 1970
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well H. Hess
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3851 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	274'	
				5 1/2"	3850'	2650'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand back from 3350' to 3320', dump 5 sacks cement. Pulled 85 joints 5 1/2" casing, total 2650'. Rock bridge from 235' to 220'. Dumped 3 1/2 yards ready mix cement. Job complete 10-29-70.

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc.
Address 320 North Park, Stafford, Kansas 67578

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack G. Paulsen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack G. Paulsen
Jack G. Paulsen
800 Sutton Place, Wichita, Kansas
(Address)

JEAN S. TAYLOR
NOTARY PUBLIC
SEDGWICK CO. KANSAS
My commission expires June 28, 1974.

Subscribed and sworn to before me this 3rd day of November, 1970.
Jean S. Taylor
Jean S. Taylor Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1970
CONSERVATION DIVISION
Wichita, Kansas

BONHOLT #1
C NE NE Section 33-30S-3W
Sumner County, Kansas

Commenced: August 13, 1970
Completed: August 22, 1970

OPERATOR - Oasis Petroleum, Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	274	Red bed and shale	Ran 13 joints of 8-5/8" casing, set @ 274' w/185 sacks cement.
274	670	Shale and red rock	
670	2770	Shale and lime	
2770	3045	Shale, lime and sand	
3045	3252	Shale and lime	
3252	3399	Lime	
3399	3851	Lime and shale	
3851	TD		Ran 123 joints of 5-1/2" casing, set @ 3850' w/150 sacks cement.

I, JAMES S. SUTTON II, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE NE Section 33-30S-3W, Sumner County, Kansas, to the best of my knowledge and belief.

James S. Sutton II

JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 24 day of August, 1970, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires February 1, 1972

Barbara J. Layton

Barbara J. Layton, Notary Public

