

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-191-22,146-0000

LEASE NAME Cline

WELL NUMBER 1

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 33 TWP. 30S RGE. 3 ~~XX~~ or (W)

COUNTY Sumner

Date Well Completed 2/8/90

Plugging Commenced 2/8/90

Plugging Completed 2/8/90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Voth Oil Company, Inc.

ADDRESS 6235 W. Kellogg, Wichita, Kansas 67209

PHONE#(316) 943-0932 OPERATORS LICENSE NO. 5898

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/7/90 (date)

by Steve Van Giesen (KCC District Agent's Name).

Is ACO-1 filled? No If not, is well log attached? Yes

Producing Formation Kansas City Depth to Top 3284 Bottom 3500 T.D. 3500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Kansas City	Dry	273	0	8-5/8	273	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole, if cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Drill to rotary total depth of 3500'. Fill with heavy mud to 750'. Set plug with 35 sacks cement. Fill with heavy mud to 300'. Set plug with 35 sacks cement. Fill with heavy mud to 60'. Set plug with 25 sacks cement. Plug rathole with 10 sacks cement. Plug water well with 10 sacks cement. Plugging complete at 6:15 P.M., February 8, 1990.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Tornado Drilling, Inc. License No. 3890

Address P.O. Box 37, Canton, Kansas 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Voth Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Randall J. Voth (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



MAR 15 1990  
3-15-90  
Notary Public  
Wichita, Kansas

(Signature) Randall J. Voth

(Address) Randall J. Voth  
6235 W. Kellogg, Wichita, ks

SUBSCRIBED AND SWORN TO before me this 13th day of March, 1999

Debra A. Ream  
Notary Public

My Commission Expires: 9-19-93

TORNADO DRILLING, INC.  
P.O. BOX 37  
CANTON, KANSAS 67428  
February 12, 1990


COMPANY: VOTH OIL COMPANY, INC.  
CONTRACTOR: TORNADO DRILLING, INC.  
FARM: CLINE # 1  
LOCATION: 4620' FSL AND 3300' FEL OF SECTION  
33-30S-3W, SUMNER COUNTY, KANSAS  
COMMENCED: JANUARY 30, 1990  
COMPLETED: FEBRUARY 8, 1990  
ELEVATION: 1339'

0	to	150	Clay & Sand	
150	to	765	Shale & Lime	
765	to	2098	Lime & Shale	
2098	to	2612	Shale & Sand	
2612	to	2882	Shale	
2882	to	3070	Shale & Lime	
3070	to	3500	Lime	DST #1 3408-3432
		3500	Rotary Total Depth	

Drill 12 $\frac{1}{4}$ " hole to 282'. Run 8-5/8" surface casing and cement at 273.29' with 185 sacks 60/40 Pozmix, 3% cc. Plug down at 11:30 P.M., January 30, 1990. Drill 7-7/8" hole to rotary total depth of 3500'. Fill with heavy mud to 750'. Set plug with 35 sacks cement. Fill with heavy mud to 300'. Set plug with 35 sacks cement. Fill with heavy mud to 60'. Set plug with 25 sacks cement. Plug rathole with 10 sacks cement. Plug water well with 10 sacks cement. Plugging completed at 6:15 P.M., February 8, 1990. Released rig.

#### CERTIFICATE

I, Henry J. Siemens, Vice President of Tornado Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Cline #1 located on the 4620' FSL and 3300" FEL of Section 33-30S-3W, Sumner County, Kansas as is reflected by the files of Tornado Drilling, Inc.



*Henry J. Siemens*  
Henry J. Siemens, Vice President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 12th day of February, 1990.

*Cynthia G. Reimer*  
Cynthia G. Reimer - Notary Public