

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

SUMNER CO, KANSAS County. Sec 30 Twp. 30S Rge. 3W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner WALTERS DRILLING CO., ET AL
Lease Name CURRY Well No. 1
Office Address 510 Orpheum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed October 11th, 1960 19
Application for plugging filed October 11th, 1960 19
Application for plugging approved October 11th, 1960 19
Plugging commenced October 11th, 1960 19
Plugging completed October 11th, 1960 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4419 feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	212	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 200' set plug with
20 sx cement & 1/2 sx hulls thru drill pipe.
Filled with heavy mud to 35' set solid bridge
with 1/2 sx hulls and 8 sx cement to base of
cellar.

Job complete 9 p.m. October 11, 1960.

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1960
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor (If additional description is necessary, use BACK of this sheet)
Address WALTERS DRILLING CO.
510 Orpheum Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
R. L. Abel (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. L. Abel
R. L. Abel of WALTERS DRILLING CO.
510 Orpheum Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of October, 1960

My commission expires August 11th, 1962. Patricia M. Edwards, Notary Public.



DRILLER'S WELL LOG

OPERATOR: WALTERS DRILLING CO. 510 Orpheum Building Wichita 2, Kansas	FARM NAME: #1 CURRY
CONTRACTOR: WALTERS DRILLING CO. 510 Orpheum Building Wichita 2, Kansas	LOCATION: C SW SE Sec. 30-30S-3W Sumner Co, Kansas
CASING: 8-5/8" @ 212' (175 sx cmt)	COMMENCED: 9-29-60 COMPLETED: 10-11-60
R.T.D. 4419'	ELEVATION: 1376' KB PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations

Soil & Red Rock	215
Shale & Shells	540
Shale & Lime	1365
Lime & Shale	1930
Shale & Lime	2355
Lime & Shale	2570
Shale & Lime	2845
Lime & Shale	3030
Shale & Sand	3180
Lime & Shale	3365
Lime	3560
Lime & Shale	3947
Mississippi Lime	4117
Lime & Chert	4175
Lime	4317
Lime & Shale	4383
Shale & Lime	4410
Simpson Sand	4419
R.T.D.	4419

CERTIFICATION

STATE OF KANSAS

COUNTY OF SEDGWICK

I, R. L. Abel of WALTERS DRILLING CO., upon oath state the the above and foregoing is a true and correct copy of the Driller's Log of the Walters #1 CURRY as described above.

R. L. Abel

R. L. Abel

Subscribed and sworn to before me on this 17th day of October, 1960.

Patricia M. Edwards

Patricia M. Edwards, Notary Public

My commission expires: August 11th, 1962.

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1960
CONSERVATION DIVISION
Wichita, Kansas