

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

STEPHENS #1
C SE SE Section 28-30S-3W
Sumner County, Kansas

Commenced: September 14, 1968
Completed: September 28, 1968

OPERATOR - O. A. Sutton

DEPTH		FORMATION	REMARKS
From	To		
0	30	Shale and sand	
30	70	Red bed	
70	100	Red bed and shale	
100	231	Shale and shells	Ran 11 joints of used 8-5/8" casing, set @ 231' w/centralizer 5' below first collar, cemented w/185 sacks.
231	1505	Shale and lime	
1505	1845	Shale and lime in streaks	
1845	2935	Shale and lime	
2935	3090	Sand and shale	
3090	3275	Sandy shale and lime	
3275	3417	Lime	
3417	3866	Lime and shale	
3866	3907	Lime	
3907	4130	Lime and chert	
4130	4235	Lime	
4235	4304	Lime and shale	
4304	4358	Sand	
4358	TD		Ran 127 joints of used 5-1/2" casing, set @ 3999'. First stage--cemented w/75 sacks, P.D. 2:30 P.M. Second stage--opened DV tool cemented w/75 sacks, P.D. 5:15 P.M. DV tool opened @ 3500'.

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1978
CONSERVATION DIVISION
WICHITA, KANSAS

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE SE Section 28-30S-3W, Sumner County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 2nd day of October, 1968, personally appeared E. E. HALL to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton, Notary Public

