

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Sumner SEC. 28 TWP. 30S RGE. 3 N/W
Location as in quarters or footage from lines:
SE NE SW

Locate Well
correctly on above
Section Platt.

Lease Owner Patrick Petroleum Company
Lease Name Thew Well No. 1
Office Address Suite 400, 120 Bldg. - Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 3-4-81
Application for plugging filed Yes
Plugging commenced 3-4-81
Plugging completed 3-4-81
Reason for abandonment of well or producing formation D & A

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled with drilling mud from 4330' TD to 295', add 1/2 sx hulls, set plug,
add 35 sx cement, add drilling mud to 40', add 1/2 sx hulls, set plug,
add 12 sx cement, 3 sx cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
3-27-81
MAR 27 1981

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R. R. A., Inc. CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
JOHN T. CRANE (employee of owner) or (owner or operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Suite 400 120 Bldg. 120 S. Market, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of March, 19 81

My Commission expires: February 1, 1983
Dorothy Crane Notary Public.

15-119-21171-0000

DRILLER'S LOG

Patrick Petroleum Corporation
 Thew No. 1
 SE NE SW
 Sec. 28-30S-3W
 Sumner Co., Kansas

Commenced; 2-22-81
 Completed: 3-4-81

Surface Casing: 278' of 8-5/8"
 Cemented w/ 300 sx., 3% cc, 2 sx. gel,
 2 sx. hulls, 75 lbs. of Flocele.

<u>FORMATION</u>	<u>DEPTH</u>
Surface	0 - 250
Red Bed & Shale	250 - 624
Shale	624 - 895
Shale & Lime	895 - 1819
-	1819 - 1980
Shale, Sand & Lime	1980 - 2162
Shale & Lime	2162 - 2649
Lime w/ shale stks	2649 - 2825
Shale & Lime	2825 - 2958
Shale & Lime	2958 - 2966
Sand	2966 - 3064
Lime & Shale	3064 - 3123
Shale & Lime	3123 - 3256
Kansas City Lime	3256 - 3358
Lime & Shale	3358 - 3480
Shale & Lime	3480 - 3715
-	3715 - 3780
Lime w/ shale	3780 - 3836
Mississippi	3836 - 3939
Lime & Shale	3939 - 4076
Lime w/ shale	4076 - 4314
Simpson Sand	4314 - 4330 T.D.

RECEIVED
 STATE CORPORATION COMMISSION

MAR 27 1981

CONSERVATION DIVISION
 Wichita, Kansas


I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

R. R. A., Inc.

R. R. Abderhalden
 By: R. R. Abderhalden

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 24th day of March, 1981.



Ada C. May
 Ada C. May