15-191-20109-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Sumner County. Sec. 25 Twp. 30 Rge. 3 (E) W (W)
Location as "NE/CNW¼SW¼" or footage from lines NE NE NW
Lease Owner Kathol Petroleum, Inc.
Lease Name Karr Well No. 1
Office Address 900 Sutton Place, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 5 19 68
Application for plugging filed January 24 19 68
Application for plugging approved 19
Plugging commenced December 9 19 68
Plugging completed 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well H. E. HEss
Producing formation Depth to top Bottom Total Depth of Well 3855 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1969
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/mud to 250'. ½ sx. hulls & plug set at 250', 25 sx. cement. Filled hole w/mud to 40', plug set and 1/2 sx hulls at 40'. 10 sx cement to surface. 2 sx cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KATHOL PETROLEUM, INC.
Address 900 Sutton Place, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Homer J. Catt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Homer J. Catt
900 Sutton Place, Wichita. Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 19 68

DIXIE LEE BROWN
NOTARY PUBLIC
STATE OF KANSAS

My commission expires June 17, 1972

Dixie Lee Brown, Notary Public.

15-191-20109-0000

KATHOL PETROLEUM, INC.

DRILLERS LOG

NO. 1 KARR

NE NE NW Section 25-30S-3W

SUMNER COUNTY, KANSAS

Commenced: 11/27/68
Completed: 12/5/68
Elevation: 1332' KB

FROM	TO	FORMATION
0	40	Surface hole
40	238	
238	305	
305	830	Shale & lime
830	1095	Shale & lime
1095	1415	Lime & shale
1415	1825	Shale & lime
1825	2145	Lime & shale
2145	2470	Shale
2470	2750	Shale & lime
2750	2955	Shale w/lime stks.
2955	3120	Shale & lime
3120	3216	Shale & lime
3216	3310	Lime & Shale
3310	3361	Lime
3361	3445	Lime
3445	3535	Lime & shale
3535	3611	Lime & shale
3611	3695	Lime
3695	3790	Lime & shale
3790	3796	Lime
3796	3806	Lime
3806	3852	Cherty Lime & shale
3852	3855	Lime
3855		Total Depth

REMARKS:

Set 8-5/8" surface casing at 238' w/175 sx 1% gel
Sun set, plug down at 10:30 PM

ELECTRIC LOG TOPS:

Kansas City	3146'	(-1814)
Marmaton	3452'	(-2121)
Mississippi	3780'	(-2449)
T.D.	3849'	(-2518)

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log recrod of the above captioned well.

Don D. Shawver

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me this 26th day of December, 1968.

Betty M. Maloney

My Commission Expires: March 22, 1971