

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Kingman County, Sec. 21 Twp. 30 Rge. 5 ~~XXX~~ (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE

Lease Owner D. R. Lauck Oil Company, Inc.

Lease Name Weathered Well No. 1

Office Address 301 South Broadway Wichita 2 Kans

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed September 21 19 55

Application for plugging filed " " 19 55

Application for plugging approved " " 19 55


Plugging commenced " " 19 55

Plugging completed " " 19 55

Reason for abandonment of well or producing formation
dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4762 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	200	8 5/8	200'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

mud 4762 - 200'

plug 200 - 196

cement 196 - 156

mud 156 - 35

plug 35 - 31

cement 31 - 6 bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1955
9-28-55
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Oil Well Cementing Co.
Address Great Bend Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John H. Knightley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley
Wichita Kans
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of September, 19 55

My commission expires Sept. 14, 1959

Elizabeth Gay
Notary Public.

PLUGGING
FILE SEC 21 T 30 R 5W
BOOK PAGE 2 LINE 38

D. R. Lauck Oil Company, Inc.

Weathered #1 SE SE NE Sec. 21-30S-5W
Kingman County Kansas

Commenced: August 31, 1955
Completed: September 21, 1955

Elevation: GR 1425, DF 1427 KB 1429

Casing Record: 200' of 8 5/8" cemented w/150 sacks

Drillers Log	Tops	
	Sample	Halliburton
Shale & shells	800	
salt & shale	905	Heebner 2957-1528 2953-1524
lime & shale	1670	Douglas 3070-1641 3066-1637
shale & shells	2250	Brown Lime 3225-1796 3220-1791
lime	2305	Stalnaker 3280-1851 3278-1849
shale & lime	2810	Kansas City 3545-2116 3544-2115
shale	2857	Base K.C. 3776-2347 3764-2335
shale & lime	3301	Marmaton Lm 3838-2409 3842-2413
shale	3387	Mississippi 4169-2740 4171-2742
lime	3400	Kinderhook 4492-3063 4489-3060
lime & shale	3550	Simpson sand 4596-3167 4596-3167
lime	4004	Arbuckle 4729-3300 4724-3295
shale & lime	4169	Rotary T.D. 4762-3333 4763-3334
whert	4190	
Cherty lime	4237	no tests
lime	4505	
shale	4575	D & A
shale & sand	4599	
sand	4651	
sand & shale	4679	
shale	4710	
shale & sand	4729	
Arbuckle	4762	
RTD	4762	

The above is a true and correct copy of the log on the Weathered No.1 well, to the best of my knowledge and belief.

John H. Knightley
John H. Knightley

Dated at Wichita, Kansas this 27th day of September 1955.

Elizabeth Gay
Notary Public

My commission expires Sept. 14, 1959

PLUGGING
WELL NO. 21 30 SW
BOOK PAGE 2 LINE 38

COMMISSION
OBSERVATION DIVISION
Wichita, Kansas