


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 18 Twp. 30S Rge. (E) 5W
Location as "NE/CNW/SW" or footage from lines C NW SE
Lease Owner Pickrell Drilling Company
Lease Name Fieser "E" Well No. 1
Office Address 705 Fourth National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 5, 1964
Application for plugging filed May 5, 1964
Application for plugging approved May 5, 1964
Plugging commenced May 5, 1964
Plugging completed May 5, 1964
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 461.1 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	226'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 225'. Set plug. Cemented with
25 sacks cement. Heavy mud to 40'. Set plug.
Cemented with 10 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1964
5-19-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PICKRELL DRILLING COMPANY
Address 705 4th National Bank Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
C. W. SEBITTS (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits
705 4th Natl Bank Bldg, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 1964

My commission expires June 21, 1966
Maxine Blackman
Maxine Blackman Notary Public.

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
 705 4th National Bank Building
 Wichita, Kansas
 LOCATION: Fieser "E" No. 1, C NW SE Section 18-30S-5W,
 Kingman County, Kansas

Rotary Drilling Commenced 4-21-64
 Rotary Drilling Completed 5-4-64

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (11 jts.) 8 5/8" surface casing set at 261', cemented with 160 sacks cement. Circulated. Completed 3:30 P.M. May 12, 1964. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

227	Shale	<u>C. F. S.</u>
900	Shale & Shells	3280
1340	Shale & Lime	3295
1550	Lime	3365
3295	Lime & Shale	3570
3375	Lime	3635
3600	Lime & Shale	3664
3807	Lime	3705
4102	Lime & Shale	4100
4134	Mississippi	4110
4195	Mississippi Lime	4125
4460	Mississippi	4550
4550	Kinderhook	4554
4558	Viola	4558
4584	Lime & Sand	4563
4611	Simpson - RTD	4592
		4611

<u>Slope Test</u>
2500
3000
3500
4000

RECEIVED
 STATE CORPORATION COMMISSION

MAY 19 1964

CONSERVATION DIVISION
 Wichita, Kansas

<u>S. L. M.</u>
3820
4157
4406

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebits Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 12th day of May, 1964, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966.

Maxine Blackman
 Maxine Blackman Notary Public