


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Take Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kingman County. Sec. 17 Twp. 30S Rge. 5 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
165' South NE/4 NW/4 NW/4  
Lease Owner Clinton Production, Inc.  
Lease Name Tonn "A" Well No. 1  
Office Address 330 N. Armour, Wichita, KS 67206  
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Date Well completed 1/14 1982  
Application for plugging filed 1/14 1982  
Application for plugging approved 1/14 1982  
Plugging commenced 1/14 1982  
Plugging completed 1/14 1982  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Metz  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Total Depth 3744 feet. Set first plug at 600 feet with  
60 sacks of 50/50 posmix cement, 3% calcium chloride;  
second plug at 260 feet with 40 sacks, 10 sacks and a  
bridge at 40 feet and 10 sacks in the rathole. Cement  
by Sun Cementing. Job complete at 4:30 a.m. on  
January 14, 1982.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kaw Drilling Co., Inc.


STATE OF KANSAS COUNTY OF SEDGWICK, ss. contractor  
K.S. Martin, President of Kaw Drilling Co., Inc. of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
K. S. Martin, President 1010 Union Center  
(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 20th day of January

My commission expires December 10, 1983

[Signature]  
Mary Susan Whaley  
Notary Public  
1-21-82  
CONSERVATION DIVISION  
Wichita Kansas



OPERATOR: Clinton Production, Inc.  
 CONTRACTOR: Kaw Drilling Co., Inc.  
 WELL NAME: Tonn "A" #1  
 LOCATION: 165' S NE/4 NW/4 NW/4 Sec. 17-30S-5W  
 Kingman County, Kansas  
 SPUD DATE: January 6, 1982  
 COMPLETION DATE: January 14, 1982

0	257	Sand and Shale
257	1493	Shale
1493	1991	Shale with Lime streaks
1991	3023	Shale
3023	3676	Lime and Shale
3676	3744	Lime
	3744	R.T.D.

Spud hole at 7:15 p.m. on January 6, 1982. Drilled 273 feet of 12½ inch hole. Ran 6 joints of new 8 5/8 inch, 20 pound casing. (Tallied at 258.23 feet.) Set at 270 feet with 200 sacks of common cement, 3% Gel and 2% Calcium Chloride. Plug down at 2:00 a.m. on January 7, 1982.

Total Depth 3744 feet. Set first plug at 600 feet with 60 sacks of 50/50 posmix cement, 3% Calcium Chloride; second plug at 260 feet with 40 sacks; 10 sacks and a bridge at 40 feet and 10 sacks in the rathole. Cement by Sun Cementing. Job complete at 4:30 a.m. on January 14, 1982.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

I, K. S. Martin, President of Kaw Drilling Co., Inc., being first duly sworn and upon my oath, state that: I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

*K. S. Martin*  
 K. S. Martin, President

SUBSCRIBED AND SWORN to before me on this 20th day of January, 1982.

RECEIVED  
 STATE CORPORATION COMMISSION  
*Mary Susan Whaley*  
 Mary Susan Whaley, Notary Public

My Commission Expires:  
 December 10, 1983

CONSERVATION DIVISION  
 Wichita, Kansas

