


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 8 Twp. 30S Rge. (E) 5(W)
Location as "NE/CNW%SW%" or footage from lines C SW SW
Lease Owner Pickrell Drilling Company
Lease Name Fink No. 1 Well No. _____
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 10, 1965
Application for plugging filed March 10, 1965
Application for plugging approved March 10, 1965
Plugging commenced March 10, 1965
Plugging completed March 10, 1965
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4587 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	223	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 220', set plug, cemented with
25 sacks cement. Heavy mud to 40' set plug.
Cemented with 10 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1965
3-19-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
C. W. Sebitts
705 4th National Bank Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March, 19 65

My commission expires June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public.

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY Rotary Drilling Commenced 2-25-65
 705 4th National Bank Bldg
 Wichita, Kansas Rotary Drilling Completed 3--9-65
 LOCATION: Fink No. 1, C SW SW Section 8-30-5W, Kingman County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (10 jts) 8 5/8" surface casing set at 223' cemented with 155 sacks cement. Circulated. Completed 11:00 P.M. February 25, 1965. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

224	Red Rock	<u>C. F. S.</u>
1010	Red Rock & Shale	3520
1454	Lime & Shale	3550
1700	Lime	3625
1920	Shale & Lime	3653
2280	Shale	3690
3060	Lime & Shale	4115
3210	Lime, Shale & Sand	4150
3520	Shale & Lime	4537
3775	Lime	4545
3850	Lime & Shale	4549
3912	Lime	4554
4118	Lime & Shale	4570
4468	Mississippi	4587
4549	Kinderhook	
4570	Viola & Simpson	<u>Slope Test</u>
4587	Simpson & RTD	2600
		3150
		3625
		4150

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 19 1965
 3-19-65
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebits, Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 12th day of March, 19 65, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebits, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

Maxine Blackman
 Maxine Blackman, Notary Public

My commission expires: June 21, 1966.