

15-095-01011-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Kingman County. Sec. 5 Twp. 30 Rge. (E) 5 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Earl F. Wakefield  
Lease Name Esther Snyder Well No. 1  
Office Address 307 Union Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 30, 19 53  
Application for plugging filed December 31, 19 53  
Application for plugging approved December 31, 19 53  
Plugging commenced December 31, 19 53  
Plugging completed December 31, 19 53  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4750 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	130	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with Rotary mud from 4750 feet to 135 feet, cemented with 15 sacks and filled with rotary mud to 30 feet, cemented with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Earl F. Wakefield  
Address 307 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Earl F. Wakefield (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield  
Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11<sup>th</sup> day of January, 1954

My Commission Expires Apr. 13, 1955

My commission expires \_\_\_\_\_

Harry S. Fickler  
Notary Public.

24-7366-5 3-53-20M

PLUGGING  
FILE SEC 5 T 30 R 5W  
BOOK PAGE 5 LINE 12

Esther Snyder #1  
Owner: Earl F. Wakefield  
Contractor: Earl F. Wakefield  
Com: 12/9/53 Comp: 12/31/53

NE NE NE 5-30 S-5W  
Kingman County, Kansas  
Casing: 130" of 8 5/8"

Elevation: 1506 D. F.

Sand & Clay	85
Shale & Shells	1380
Lime & Shale	3232
Sandy Lime & Shale	3345
Lime & Shale	3553
Lime (K. C.)	3667
Lime & Shale	3805
Lime	3840
Lime & Shale	4125
Shale	4156
Lime (Mississippi)	4235
Lime & Shale	4294
Lime	4370
Shale	4385
Lime & Shale	4420
Shale	4459
Lime	4470
Shale	4574
Lime (Viola)	4586
Sand (Simpson)	4615
Sand & Shale	4650
Shale, Sand & Lime	4675
Shale & Sand	4713
Lime (Arbuckle)	4750
Total Depth	4750

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I Herby agree and certify that the above is a true and correct copy of the log drilled on the Esther Snyder #1 well, located NE NE NE 5-30 S-5W, Kingman County, Kansas.

Earl F. Wakefield

Sworn and subscribed before me this 11th day of January, 1954.

My Commission Expires Apr. 18, 1955

Henry D. Ficker

PLUGGING  
WELL SEC. 5 T 30 S W  
BOX PAGE 2 LINE 12