

RECEIVED
AUG 05 2003
KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-173-20,733-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Bear Petroleum, Inc. KCC LICENSE # 4419
(owner/company name) (operator's)

ADDRESS P.O. Box 438 CITY Haysville

STATE KS ZIP CODE 67060 CONTACT PHONE # (316) 524-1225

LEASE Fenster WELL# 2 SEC. 12 T. 29 R. 1 (East/West)

SE - NW - NE SPOT LOCATION/0000 COUNTY Sedgwick

4290 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

4290 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 217 CEMENTED WITH 150 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 3614 CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3274-81' Mississippi

ELEVATION 1291 T.D. 3614 PBD 3583 ANHYDRITE DEPTH ?
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Dump sand to 3334', dump bail 4 sax cement, shoot and pull pipe, run in hole tubing to 267', and circulate cement to surface. 60/40 poz 6% gel.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dick Schremmer PHONE# (316) 524-1225

ADDRESS P.O. Box 438 City/State Haysville, KS 67060

PLUGGING CONTRACTOR Braden Petroleum & Well Plugging KCC LICENSE # 32475-6957
(company name) (contractor's)

ADDRESS P.O. Box 282, Burden, KS 67019 PHONE # (620) 438-2856

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) unknown

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-1-03 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Bear Petroleum, Inc.
PO Box 438
Haysville, KS 67060

August 06, 2003

Re: FENSTER C #2
API 15-173-20733-00-00
SENWNW 12-29S-1W, 4290 FSL 4290 FEL
SEDGWICK COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231