

15-119-10111-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*JL*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 22 1972 5-22-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company Inc.

Complete Address 200 W. Douglas, Wichita, Kansas

Lease Name Plains Townsite Well No. 1

Location C SE SE Sec. 16 Twp. 32 Rge. 30 (E) (W)

County Meade Total Depth 5815'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated None

Plugging Contractor Knight Casing Pulling Inc.

Address Chase, Kansas License No. 624

Operation Completed: Hour 3:30PM Day 13 Month 5 Year 1972

The above well was plugged as follows:

10 3/4" to 1590' circulated w/ cement. 7" to 5790' cemented.

Top Perforations 5136' Plug bottom w/ 20 sacks cement.

Top of cement 4860' Mud 4860' to 900'

Spotted 40 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Halliburton Pump

Pulled 2700' of 7" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edgar J. Egan*  
Well Plugging Supervisor

INVOICED

DATE 5/25/72

INV. NO. 5735-W