

SP

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 14 1972 1-14-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Helmly & Prather Oil Corporations  
Complete Address 518 Petroleum Bldg., Amarillo, Texas 79100  
Lease Name Cottrell Well No. 1  
Location C SW SW Sec. 2 Twp. 32 Rge. 30 (E) (W)  
County Meade Total Depth 5677'  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X  
Other well as hereafter indicated None  
Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511  
Operation Completed: Hour 6:00PM Day 12 Month 1 Year 1972

The above well was plugged as follows:

8 5/8" to 1574' circulated w/ cement. 4 1/2" to 5677' cemented.  
Top perforations 4788' Plug bottom w/ 20 sacks cement.  
Top of cement. 4600' Mud 4600' to 1000'  
Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'  
Plug, Halls & 15 sacks cement 45' to 0'. Company Pump  
Pulled 3003' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1-14-72  
INV. NO. 52005-11