

KANSAS

*3*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 11 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Edwin G. Bradley

Complete Address: 826 Union Center, Wichita, Kansas

Lease Name Easum Well No. 1

Location C SE NW Sec. 27 Twp. 32 Rge. 29 (W) (W)

County Meade Total Depth 6414'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:00PM Day 8 Month 6 Year 1968

The Above well was plugged as follows:

8 5/8" to 1615' circulated w/ cement. 4 1/2" to 5830' cemented.

Top perforations 5674' Plug bottom w/ 20 sacks cement.

Top of cement 5440' Mud 5440' to 800'

Spotted 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Hulls & 15 sacks cement 45' to 0' Halliburton Pump Truck.

Pulled 3445' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eves  
Well Plugging Supervisor

DATE 6/11/68

INV. NO. 7926-4