

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT
K-189-1062-0000

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1964
9-21-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Walter Kuhn Drilling Co.

Complete Address: 726 Union Center. Wichita, Kansas

Lease Name Curtis Well No. # 1

Location C NE Sec. 25 Twp. 31 Rge. 39 (E) / (W)

County Stevens Total Depth 2622'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Co.

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 5 PM Day 18 Month 9 Year 64

The Above well was plugged as follows:

10 3/4"-530'. Circulated w/cement. 5 1/2"-2405'. 7"-2405'.

Packer 2399' to 2405'. 5 1/2" linner 2405' to 2620'

Bottom sanded to 2441' 20 Sax.cement top cement 2292'

Mud 2292' to 530' Spotted 35 Sax.cement 530' to 450'

Mud 450' to 25' Plug,Hulls,15 Sax.cement 25' to 0

Company Pump. Pulled 2204' 5 1/2" pipe. Pulled 1007' 7" pipe.

Cut pipe off 5' below ground level. weld plate on top.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/21/64
INV. NO. 9831-W

Signed: [Signature]
Well Plugging Supervisor