


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-129-00073-0000

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pan American Petroleum Corporation

Complete Address Box 432, Liberal, Kansas 67901

Lease Name Wratil Gas Unit "B" Well No. 1

Location SW NE Sec. 22 Twp. 31 Rge. 40 (E) (W)

County Morton Total Depth 6085'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 22 Month 11 Year 1969

The above well was plugged as follows:

8 5/8" to 1718' circulated w/ cement. 5 1/2" to 6030' cemented,

Top perforations 5202' Plug bottom w/ Bridge Plug & 2 sacks cement.

Top of cement 5146' Mud 5146' to 1743'

Spotted 20 sacks cement 1743' to 1693' Mud 1693' to 800'

Spotted 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2685' of 5 1/2" casing

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edward Eves
Well Plugging/Supervisor

DATE 11/24/69

INV. NO. 913-W